

(6) Neither the lessee nor his servants shall enter the Farm and Gardens, etc., either before sunrise or after sunset.

(7) The lessee *shall not cut branches* and collect only the fallen Hunge leaves.

In the event of breach of any of the above conditions, the lease will be liable to be cancelled and the lessee fined to the extent the Chief Commandant, Mysore State Troops, thinks fit.

J. J. MALLICK
Superintendent

MYSORE STATE RAILWAY.

OFFICE OF THE DISTRICT ENGINEER, MYSORE STATE RAILWAY, BANGALORE CITY.

Abstract Notification dated 18th August 1939.

The attention of the public is invited to the detailed notification, published on pages 1604-1605 of Part VI of the *Mysore Gazette*, dated 17th August 1939 re collecting and spreading broken stone ballast on Bangalore Hindupur Section for trestling between miles 134/13-16 and 145/14-15.

The last date for receiving tenders is 1st September 1939 up to 12 NOON.

In modification of paras 13 and 14 of Notification of 31st July 1939, please read as under:—

Item 13.—The work of collection of metal ballast should be completed by 75 per cent by the end of December 1939, and 90 per cent by the end of January and the balance by end of February 1940.

Item 14.—Contractors should specify in their tender the quantity they propose to collect at the nearest Depot or mileage from where it can be spread between miles 134/13-16 and 145/14-15. The collection may extend from 134/15-16 to mile 158 also.

Contractors should use their discretion in mentioning the places where they are going to collect ballast. The places should be such as to facilitate easy loading of the ballast in trucks. All the charges of levelling up the ground, etc., for stacking the materials will be borne by the contractors.

The time of sending the tenders has been extended up to 18th September 1939, Monday, 4 P.M."

V. HANUMANTHA RAO,
Ag. District Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, S. T. RAILWAY CONSTRUCTION DIVISION.

Correction Memo dated 26th August 1939.

Tender Notification dated 21st August 1939, for constructing Ballast Walls in Cuttings on S. T. Railway published on page 1701, Part VI of the *Mysore Gazette*, dated 24th August 1939.

Page 1701, Para 11, Line 2.—Read "and" for "or".

Page 1701, Para 14.—Read "stones" for "stores".

Page 1702, Description of work.—After '1 Ballast Wall with granite stone 12" wide and 9" deep' insert "or" and read '2 Ballast Wall with laterite stones 12" wide and 9" deep'.

Tender Notification dated 21st August 1939, for forming a Level Crossing on Bangalore-Honnava Road near Talaguppe.

Page 1703 of *Mysore Gazette*, Part VI.—Read "soling" for "soiling" under '2. Collection of materials. item (a)' and "S.ft." for "C.ft." under '3. Consolidation. against item (a)' in column Description of work'.

M. R. KRISHNAMURTHI,
Executive Engineer.

OFFICE OF THE DISTRICT ENGINEER, MYSORE.

Notification dated 23rd August 1939.

Sealed tenders will be received at the Office of the District Engineer, Mysore State Railway, Mysore, up to 3 P.M. on Monday the 18th September 1939, from contractors for works in connection with "Constructing quarters for Menials at Channapatna Railway Station."

2. Tenders should be submitted only in special forms which can be obtained from the Auditor, Mysore State Railway, Mysore, on payment of rupee one, being the cost of the form.

3. The tender must be accompanied by a receipt of payment of earnest money of Rs. 50, to the Auditor, Mysore State Railway, Mysore, mentioning the above work, either in cash, Government Bonds, Debenture bonds of Local Bodies and the Land Mortgage Banks in the State, guaranteed

by Government, or Fixed Deposit Receipts of Bangalore City Co-operative Bank, Ltd. No cheques will be received.

4. Tenders which give rates "as per estimate" or so much per cent above or below estimate rates will not be considered.
5. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.
6. The name of the accepted tenderer will be posted on the Notice Board of the District Engineer's Office, as soon as it is approved. No enquiries regarding the acceptance or rejection of a tender will be replied to.
7. Detailed estimates, plans and specifications, conditions of works and conditions of Schedule Agreement may be seen at the District Engineer's Office, Mysore State Railway, Mysore, on all working days between 2-30 and 4-30 P.M. When in doubt, the tenderers should always ask for particulars and details.
8. The Contractor whose tender is accepted shall, before the acceptance of the Schedule Agreement deposit with the Auditor, Mysore State Railway, Mysore, cash or Government Promissory Notes endorsed in favour of the General Manager, Mysore State Railway, Mysore, the sum of Rs. 50 as security for the due fulfilment of the agreement in addition to Rs. 50, *vide* para 3 (Cash amount will not carry any interest). No cheques will be accepted.
9. The earnest money (referred to in para 3 above) of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of, while that of the successful tenderer will be accepted as part security for the due fulfilment of the terms of the Agreement.
10. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore State Railway, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reason therefor, any or all the tenders or any portion of a tender, and also the right to accept a tender for any individual item or items without accepting the whole tender unless the tenderer expressly states in his tender that it must be accepted or rejected as a whole.
11. The work should be started within a week from the date of acceptance of the Schedule Agreement and should be completed within two months with a guaranteed monthly rate of progress of Rs. 1,000.
12. Within a week from the date of acceptance of tender, the successful tenderer is required to execute the usual Schedule Agreement, in default of which his tender will be considered as cancelled and the earnest money forfeited to Government.
13. There should be no corrections or erasures in the tender in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.
14. Rates once tendered cannot be enhanced on any account. Rates for non-tendered and non-estimated items shall be as per minimum schedule of rates of the Railway Department, or those fixed by the District Engineer, after working out data with ten per cent for Contractor's profit.
15. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any item of work or specification, the decision of the Superintendent, Way and Works, Mysore State Railway, Mysore, shall be final.
16. The accepted tenderer must make his own arrangements in advance for payment of royalties, toll, octroi, etc., in case he quarries stone, earth, kankar, sand, etc., from Railway, Government or Forest land for use on this work, as this Department will not concern itself regarding the payment, or recovery of royalty, tolls, octroi, etc.
17. No claims for damages for delays caused by Officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental Officers, will, however, be considered on the merits of each case.
18. The contract should not be sublet.

Note A.—

The Contractor should at his own cost—

- (1) Provide bamboos, rods, stakes, ropes and labour required in setting out the work.
- (2) Provide mortar mill and shed to keep materials under cover and also for workmen.
- (3) Arrange for protecting work during inclement weather.
- (4) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (5) Supply requisite temporary lights, water cisterns, water shoots, coverings to masonry sieves, parabs or measures, shoring and other requisite protection during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide latrines, drainage, etc.
- (7) Clean away all dirt, rubbish superfluous materials and debris as they accumulate.

- (8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
- (9) Wash floor at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

Note B. —

- (1) In general, works should be executed as per Marryat's Specifications.
- (2) Measurement for doors, windows and ventilators will be given for clear inside dimensions between frames only.

Schedule.

Sl. No.	Description of work	Approximate quantity	Unit
<i>Constructing one Block of two units for Menials' Quarters at Channarayana Railway Station.</i>			
<i>Details for one block.</i>			
1	Earthwork excavation in all soils and filling in basement	780 C.ft.	1,700 C.ft.
2	Concrete broken granite stone jelly in lime mortar	310 "	100 "
3	Burnt brick in chunam mortar	900 "	100 "
4	Burnt brick in mud	1,400 "	100 "
5	Burnt stone slabs one line dressed and fixed in chunam mortar	184 S.ft.	S.ft.
6	Teakwood doors with battened shutters 1" thick, hinges, tower bolts, etc., complete	85 "	"
7	Teakwood windows with 1" thick battened shutters in four halves $\frac{3}{4}$ " sq. M. S. bars fixed at not more than 4" centre to centre rings, hooks, etc., complete	35 "	"
8	Teakwood ventilators with 1" thick battened shutters, $\frac{3}{4}$ " square M. S. bars, rings, hooks, etc., complete	18 "	"
9	Teakwood wrought and put up including wood oiling, two coats	26.5 C.ft.	C.ft.
10	Conveying, noisting and fixing 41½ lbs. section rails	18 R.ft.	R.ft.
11	Roofing with first class Mangalore pattern Yelahanka tiles on Teak reepers 2"×1" including wood oiling to reepers and providing chunam borders, Teakwood wind ties, etc., complete. R.M.C. will be given for tiles from Yelahanka	760 S.ft.	100 S.ft.
12	Ridge tiles set in mortar and cement pointed. R.M.C. will be given for tiles	35 R.ft.	R.ft.
13	Chunam plastering	3,500 S.ft.	100 S.ft.
14	White and colour washing, two coats	3,500 "	100 "
15	Cement plastering $\frac{1}{2}$ " thick	170 "	100 "
16	Supplying and fixing granite stone p-stile and mortar	Two	Each
17	Flooring with 4" thick concrete broken stone jelly in chunam mortar and plastered over with $\frac{1}{2}$ " thick cement	525 S.ft.	100 S.ft.
18	Flooring with 4" thick burnt stone slabs 2 lines dressed and fixed on a bed of 4" thick chunam concrete and cement pointing complete	40 "	100 "
19	Providing and fixing smoke tiles in mortar and cement pointed, R. M. C. will be given for tiles	8 Nos.	Each
20	Providing ovens	2 "	"
21	Providing and fixing 22 B. W. G. zinc sheet valley gutters fixed over $\frac{1}{2}$ " thick teakwood planks including cement plastering	25 R.ft.	R.ft.
22	Doors with teakwood frames and 22 B.W.G. plain G. I. sheet shutters, tower bolts, hinges, etc., complete	50 S.ft.	S.ft.
23	Silicate chocolate painting, two coats	450 "	100 "
24	Reinforced cement concrete terrace 3' thick with 2" thick surki concrete and cement plastering etc. complete	88 "	100 "
25	Wire cut brick pillars 9" sq. including base and capital including plastering, etc., complete. Height of pillar 7'-6"	2 Nos.	Each
26	Reinforced cement concrete slabs 1" thick with neat finish as per design and fixing complete	34 S.ft.	S.ft.
27	Brick masonry bund 9" high as per design including plastering	20 R.ft.	R.ft.
28	Brick in mortar cornice 6" thick including plastering	25 "	"
29	Cement concrete seats including plastering and fixing 14"×9"×9"	6 Nos.	Each
30	Boxing 41½ lbs. rail girders with brick in cement mortar and plastering, etc., complete	20 R.ft.	R.ft.
31	Providing 'U' shaped cement drain 4½" wide including cement plastering, complete	20 R.ft.	R.ft.

Sl. No.	Description of work	Approximate quantity	Unit
<i>Constructing Sweepers' Quarters 1 Unit at Channarayana Railway Station.</i>			
1.	Earthwork excavation in all soils and filling in basement ..	400 C.ft.	1,000 C.ft.
2.	Concrete broken granite stone jelly in lime mortar ..	163 "	100 "
3.	Burnt brick in chunam mortar ..	354 "	100 "
4.	Burnt brick in mud ..	535 "	100 "
5.	Burnt stone slabs one line dressed and fixed in chunam mortar ..	61 S.ft.	S.ft.
6.	Teakwood doors with battened shutters 1" thick, hinges, tower bolts, etc., complete ..	18 "	"
7.	Teakwood windows with 1" thick battened shutters in four halves, $\frac{3}{4}$ " sq. M. S. bars fixed at not more than 4" centre to centre, rings, hooks, etc., complete ..	12 "	"
8.	Teakwood ventilators with 1" thick battened shutters, $\frac{3}{4}$ " sq. M. S. bars, rings, hooks, etc., complete ..	6 "	"
9.	Teakwood wrought and put up including wood oiling, two coats ..	17 C.ft.	C.ft.
10.	Roofing with first class Mangalore pattern Yelahanka tiles on teak reapers 2" x 1" including wood oiling to reapers and providing chunam borders, teakwood wind-ties, etc., complete, R.M.C. will be given for tiles from Yelahanka ..	384 S.ft.	100 S.ft.
11.	Ridge tiles set in mortar and cement pointed. R.M.C. will be given for tiles ..	21 R.ft.	R.ft.
12.	Chunam plastering ..	1,465 S.ft.	100 S.ft.
13.	White and colour washing, two coats ..	1,465 "	100 "
14.	Supplying and fixing granite stone pestle and mortar ..	1 No.	Each
15.	Flooring with 4" thick concrete broken jelly in chunam mortar and plastered over with $\frac{1}{2}$ " thick cement ..	142 S.ft.	100 S.ft.
16.	Providing and fixing smoke tiles in mortar and cement pointed. R.M.C. will be given for tiles ..	2 Nos.	Each
17.	Providing ovens ..	1 No.	"
18.	Silicate chalcote painting, two coats ..	100 S.ft.	100 S.ft.
19.	Plain eave board 9" wide $\frac{3}{4}$ " thick including painting and fixing complete ..	36 R.ft.	R.ft.
20.	Providing T. W. pendants ..	4 Nos.	Each
21.	Do T. W. Finials ..	2 "	"
22.	Do 'U' shaped cement drain 4 $\frac{1}{2}$ " wide including cement plastering, complete ..	12 R.ft.	R.ft.

Note.—Departmental materials such as Teakwood doors, scantlings, tiles, slabs, etc., issued to be used on works.

D. V. NARASIMHA RAO,
District Engineer.

OFFICE OF THE DEPUTY COMMISSIONER, HASSAN DISTRICT.

Notification No. C. 5027-38, dated the 27th August 1939.

It is hereby notified for the information of the public that the Travellers' Bungalows at the undermentioned places will be reserved for the use of the Dewan of Mysore on the dates noted against each, in connection with his tour in Hassan District.

- | | | |
|----|-----------------|---|
| 1. | Chennarayapatna | 21st September 1939. |
| 2. | Hole-Narsipur | 21st September 1939. |
| 3. | Hassan | 21st September 1939 to 23rd September 1939 (both days inclusive.) |
| 4. | Belur | 23rd September 1939. |
| 5. | Arsikere | 24th September 1939. |

T. RAMAIA,
Deputy Commissioner.